November 6, 2026

ATTENTION ALL SUBMITTERS AND PLAN HOLDERS

San Juan County
Conservation Land Bank
350 Court St #6,
Friday Harbor, WA 98250

TOWN OF FRIDAY HARBOR TO ZYLSTRA LAKE MULTIMODAL TRAIL
BEAVERTON MARSH SEGMENT

Addendum No. 1

The following changes are hereby made to the Contract Documents for:

Beaverton Marsh Multi-Modal Trail Project

Call for Bids

1. On page 5 of Call for Bids, bullet 1 is revised to read:
   1. PRE-BID CONFERENCE: This is ~~MANDATORY~~ HIGHLY RECOMMENDED and will be held for this project

Special Provisions

2. On page 36 of Special Provisions, table is revised to read:

Permit or Approval	Permit #	Issuing Agency	Issued	Expires
Bald Eagle Nest Disturbance Permit	PER39346133	U.S. Fish and Wildlife Service	10/29/2026	8/31/2027

3. On page 104 of Special Provisions, line 28 is revised to read:
   All non weathering steel material finishes shall be hot-dip galvanized in accordance with ASTM A123.

4. On page 115 of Special Provisions, lines 22 to 52 is deleted:
   ~~**Painting**~~

   ~~**Construction Requirements**~~
   ~~Section 6-07.3 is supplemented with the following:~~

(******)
Painting Wetland Crossing Structures

Painting Steel

This Work consists of preparing the surface, furnishing, and applying paint in the shop and repairing the coating in the field to all piling and structural steel for the following Structure(s):
Wetland Crossing Prefabricated Steel Truss
Steel Cross Beams
Steel Cover Plates
High Strength Bolts, Nuts and Washers, and Welds
Steel Sill Plates
Helical Piles

Paint Systems

(WSF February 20, 2019)
Painting Steel – Piling

Paint materials for structural steel for landing aids and piling shall be one of the following systems:

Carboline Company:
Carbozinc 808 - shop application only
Carboguard 635
Carbomastic 615 - field application only

5. On page 116 of Special Provisions, lines 22 to 52 is deleted:

Devoe Coatings Company:
Catha-Coat 302H
Devran 261 QC

International Paint Company:
Interzone 954
Sherwin-Williams Company:

Corothane 1 Galva-Pac Zinc Primer
Dura-Plate 235
Dura-Plate 154
Envirolastic AR425 - field application only
Corothane 1 Coal Tar

Tnemec Company:
Series 90-97 Tneme-Zinc
Series N69 Hi-Build Epoxoline II
Series 1 Omnithane
Series 446 Permashield MCU

Wasser High Tech Coatings:
MC-Zinc 100 - shop application

~~MC-MIOZinc 100 - field application~~
~~MC-Ferrox A 100 10 MC-Ferrox B 100~~
~~MC-Luster 100 12 MC-Tar 100~~

6. On page 127 of Special Provisions, lines 8 to 18 is deleted:
   ~~**Mulch and Amendments**~~
   ~~Section 8-02.3(6) is supplemented with the following:~~

   ~~(******)~~
   ~~**Mycorrhizal Fungi**~~
   ~~Prior to installation and under supervision of the Engineer, inoculate all plants with mycorrhizae in accordance with the manufacturer's recommendations.~~

7. On page 129 of Special Provisions, lines 36 to 45 is revised to read:
   A. Plant Establishment
   1. Pruning
   ~~2. Fertilizing~~
   3. Watering - amount in inches per week (Contractor provide watering plan)
   4. Weed Control ~~and Chemical Application - post and pre-emergent~~ (Contractor provide weed control plan)
   5. Litter and Debris Removal
   ~~6. Staking/Guying Removal~~
   7. Erosion Control Methods and Procedures
   8. Plant Replacement to Maintain 100% Survival
   9. ~~Vandalism and~~ Contractor Accidental Damage Repair

8. On page 130 of Special Provisions, lines 1 to 26 is deleted:
   ~~Plant Establishment - Second year: This work consists of continued plant establishment maintenance within the project limits.~~

   ~~Plant Establishment - Third year: This work consists of continued plant establishment maintenance within the project limits.~~

Plans

1. Sheet 64 (Structural Notes) is revised. Replace the respective pages with the attached sheet.

San Juan County CLB web page updates:

2. Updated Environmental Documents
3. Added Structural Calculations
4. Added Plan Holders List